# **Specification**

## 1.6 MV DC test system

#### **System parameters:**

Rated voltage - 1600 kV

Rated current - 10 mA

Rated power - 16 kW

Voltage tolerance % < 3 voltage above 160 kV

Duty cycle at rated power - continuous operation

### Mains supply

Power circuit 2PE, 400 V, 50Hz, 60 kVA

Control circuit - 3NPE, 230/400 V, 50Hz, 3 kVA

#### **Operating conditions**

Ambient temperature from 5 to 40°C

Max. relative humidity from 40 to 90% (no condensation)

Height above sea level  $m \le 1000$  (at higher altitude with reduced voltage)

Ambient temperature for storage and transportation from -10 to  $50^{\circ}$ C

Installation indoor, stationary